



ITEM	NO.	PART#	MATERIAL	ITEM	NO.	PART#	MATERIAL
XX	3		Cutout/arrestor 14.4		25'		#Soft six
XX	1		Transformer Platform		6		Eyenuits, 5/8"
XX	4		Timbers 18'		3		Clamp top
XX	9		D.A. Bolts	rp5	26		Perch Guard 30"
XX	6		Epoxilators	rp8	2		Perch Guard Pole Top Cone
XX	6		Upset Bolt				
XX	1		Insulator Spool				
XX	200'		#2 Jumper wire				
XX	29		Washers, 2x2				

NOTE:  
If timber spans are greater than 16,' additional perch guards are required.

14.4/ 24.4 KV  
4160 PRIMARY DELIVERY

RUS  
03/17/2009  
Rev. A



VG3.5G